


- NOTES:
1. DECK SHALL BE CONSTRUCTED OF PRESSURE TREATED WOOD MEMBERS AND GALVANIZED FASTENERS.
 2. OUTER BAND BOARD AND LEDGER BOARD SHALL BE 2" X 12" DOUBLED TOGETHER.
 3. JOIST MEMBERS SHALL BE 2" X 10" AND WILL BE USED IN CONJUNCTION WITH GALVANIZED JOIST HANGERS.
 4. LEDGER BOARDS SHALL BE FASTENED TO THE EXISTING HOUSE WITH 3/4" CARBARGE GALVANIZED BOLTS, NUTS AND WASHERS.

5. DECKING BOARDS SHALL BE 5/4" PRESSURE TREATED BOARD WITH 1/8" TO 1/4" SPACING BETWEEN THEM FOR DRAINAGE.
6. STEPS UP TO DECK WILL BE PROVIDED WITH APPROXIMATELY A 7" RISER AND 10" TREAD.
7. RAILING/OD DECK SHALL CONSIST OF TOP RAIL OF 2 X 6" PRESSURE TREATED WOOD, 2 X 4" TOP AND BOTTOM HORIZONTAL MEMBERS, AND 2 X 2" PICKETS SPACED 6" O.C.
8. POSTS SHALL BE 6 X 6" PRESSURE TREATED PINE ATTACHED WITH 3/4" CARBARGE BOLTS.
9. POSTS SHALL BE FASTENED TO TOP OF GALVANIZED POST BASE WHICH RESTS ON TOP OF 8" REINFORCED CONCRETE FOOTER 12" IN DIAMETER.

NO.	DATE	REVISION	BY

PARHAM - DECK RENOVATION
708 EAST ARTIC AVE.
 FOLLY BEACH, SC 29439



ESP CONTRACTING
 WWW.ESPCONTRACTING.NET
 801 FREEDOM ROAD
 CHARLESTON, SC 29412
 (843) 670-2021

S1
 SHEET NO.

PROJECT: FOLLY DECK
 DATE: 6/23/09
 SCALE: 1/8" = 1'-0"
 DWG. BY: PRB
 CHD. BY: